

SCHEDULE OF PRICES (for completion)



Department of
Conservation
Te Papa Atawhai

TENDER FOR - Mintaro Suspension Bridge and Track

CONTRACT Number - TBC

Item	Description	Unit	Quantity	Rate	Amount
1	Preliminary and General				
1.1	Site establishment and disestablishment	LS	1		6400
1.2	Set out of bridge, anchors	LS	1		1437
2	Suspension Bridge Construction				
2.1	Supply and install true left tower to include tower tieback cable.	LS	1		8700
2.2	Supply and install true right tower including stairs and tower tieback cable.	LS	1		8700
2.3	Supply and install true left rock anchor - including drilling and grout.	LS	1		6700
2.4	Supply and install true right timber dead-man anchor.	LS	1		5100
2.5	Supply and install main wire ropes and main wire rope hardware.	LS	1		6200
2.6	Supply and install load spreader wire ropes and all hardware.	LS	1		5400
2.7	Supply and install transoms and hangers.	LS	1		9100
2.8	Supply and install bridge decking and barriers (decking, kerbing, load spreaders, horizontal bracing, mesh, barrier cable, galvanised pipe handrail, infill and all fixings and brackets included).	Lin m	28.8m		61820
3	Track Construction				

